

**TOWN OF BURLINGTON, MASSACHUSETTS  
APRIL 29, 2022  
ADDENDUM NO. 1  
TO  
CONTRACT DOCUMENTS  
FOR  
2022 DRAINAGE & WATER IMPROVEMENTS  
CONTRACT #22C-411-0051**

The following changes and additional information are hereby made part of the Contract Documents:

Under *Item 269.12 – 12” Perforated HDPE Subdrain Pipe* on page 39, **add** the following:

An existing 4” SDR 35 PVC drain service from #3 Arnold Terrace connects into the 12” pipe proposed to be replaced. Work under this item will include furnishing and installing a 12” x 4” HDPE pipe tee and all other piping, couplings, and any other appurtenances necessary to properly reconnect the existing 4” SDR 35 PVC drain to the new 12” HDPE drain pipe. The location of this connection will be located during construction. This work will be considered incidental to the Contract price.